

Pre-Packaged



Mechanical, **E**lectrical & **C**ontrols **H**ousing **S**ystems

for Waste Water Lift Stations



Patent Pending

by DENYG Mechanical

Your pre-packaged system consists of:



Mechanical:

Standard equipment to consist of check valves, plug valves, air release valve, flow meter, venting and all necessary piping and accessories.

Standard access hatch c/w safety grating for pump removal and wet well access.



Electrical and Controls:

Standard equipment to consist of power entrance, distribution, heating and ventilation.

Pump control panel for operation and monitoring.

All necessary piping and junction boxes for easy pump removal when required.



by DENYG Mechanical



Housing:

Standard equipment to consist of a heated and weather proof fibreglass enclosure that is esthetically suitable for residential area. (Industrial exterior finish also available)

The enclosure is divided in two separate rooms: a section limited to mechanical equipment and pump junction boxes and a “**WALK-IN**” section that houses all the electrical panels and controls.

The pre-packaged system also includes a pre-cast concrete cover c/w an aluminium access frame and safety grating.

The entire structure is self-balancing on the wet well and requires no extra foundation.

Available in 6’ , 7’ and 8’ diameter wet well. Adaptable to existing structures and various submersible pump manufacturers.

by DENYG Mechanical

In collaboration with:



Delivery and installation included!

GN LEBLANC
CONSTRUCTION LTD

506-532-9345

DENYG
MECHANICAL

www.denyg.com

info@denyg.com



1691 Route 133, Grand-Barachois, NB E4P 8E4

You ask, we build!